Item No.	Description / Scope Specifications	Unit of Measure	Qty	Rate (ZAR)	Amount (ZAR)
1.0					
1.1	Health & Safety Management: SHEQ induction, legal compliance, noise exposure control, OHS Act file compilation & approval	Sum	1		
1.2	Environmental Management: ISO 14001 EMS file, pollution prevention, NEMA compliance & housekeeping management	Sum	1		
1.3	Quality Assurance & Control: Quality Control Plans (QCP) compilation, QM 58 & OMOP4497 compliance, AIA witnessing coordination, and Quality Data Book generation (EN10204 3.2 certification, PED, steel mill certificates)	Sum	1		
2.0					
2.1	90 Degree Seamless Bend (Bends 33 & 34,	Off	4		

	Radius 1750 mm) Material: 11CrMo9-10 (1.7383) to EN10222-2 TC2 ID: 1070 mm, Min WT: 58 mm | Stock No: 785136 Design: 540°C @ 4.3 MPa | Full NDT & Hard Stamped				
2.2	36 Degree Seamless Bend (Bend 35, Radius 1750 mm) Material: 11CrMo9-10 (1.7383) to EN10222-2 TC2 ID: 1070 mm, Min WT: 58 mm | Stock No: 785029 Design: 540°C @ 4.3 MPa | Full NDT & Hard Stamped	Off	2		
2.3	54 Degree Seamless Bend (Bend 36, Radius 1750 mm) Material: 11CrMo9-10 (1.7383) to EN10222-2 TC2 ID: 1070 mm, Min WT: 58 mm | Stock No: 785028 Design: 540°C @ 4.3 MPa | Full NDT & Hard Stamped	Off	2		
3.0					

3.1	Anti-corrosive storage packaging, heavy-duty bundling/securing, loading, specialized transport to Matla Power Station, and offloading coordination (incl. 72-hr prior QC notification & store delivery notification)	Sum	1		
	Total Amount				