THEMBISILE HANI LOCAL MUNICIPALITY

PROJECT No: THLM/SCM17/2026-2027/WS01

APPOINTMENT OF A PANEL OF SERVICE PROVIDERS TO PROVIDE TEMPORARY WATER SUPPLY THROUGH WATER TANKERS WITHIN THEMBISILE HANI LOCAL MUNICIPALITY AS AND WHEN REQUIRED FOR A PERIOD OF 36 MONTHS.

SCOPE OF WORK

The scope of work will entail: provide temporary water supply through water tankers for Thembisile Hani Local Municipality as follows:

1. **SCOPE OF CONTRACT**

1.1. To deliver water to Thembisile Hani Local Municipality's villages through water tankering, on an as and when required basis.

2. **HEALTH AND SAFETY**

2.1. Occupational Health and Safety Act 1994 (Act No. 85 of 1993)

2.1.1. The Service Provider shall comply with the Occupational Health and Safety Act 1994 (Act No. 85 of 1993) and with its Construction Regulations of 2014.

2.1.2. All the works included in this Contract shall, for the purpose of complying with the OHS Act and the Construction Regulation, be deemed to be "construction works".

3. **WATER TANKER CLEANING**

Water tankers must be thoroughly cleaned on a quarterly basis to ensure water quality and safety. Service providers are required to submit photographic evidence (before, during and after cleaning) with clear date stamps for each tanker. In addition, a certificate of cleanliness from an accredited Water Laboratory must be provided for each cleaning cycle. All submitted evidence and certificates will be subject to verification by a Thembisile Hani Local Municipality (THLM) official. Failure to comply with these requirements may result in suspension or termination of the contract.

4. **WATER TANKER: ROADWORTHY, LICENCE AND IDENTIFICATION**

4.1. All vehicles to be used for this contract are always to be roadworthy and licensed for use on public roads. All vehicles to be used for this contract must conform to the Road Traffic Act RTA, Act 93 0f 1996.

4.2. A standby water tanker must always be available for immediate deployment in the event of a breakdown or when scheduled servicing is required, to ensure uninterrupted water delivery.

4.3. All vehicles must be clearly branded with the municipality's name and logo, as per municipal branding guidelines. Branding must be visible and maintained in good condition throughout the contract period for monitoring purposes.

4.4. All vehicles must be equipped with a calibrated water level measuring device that accurately records and displays the volume of water contained in the tanker. The device must be installed by a qualified technician, always remain fully operational, and be readily accessible for inspection by the municipality.

4.5. All vehicles must be equipped with a real-time tracking device to monitor routes, delivery times, and vehicle locations, distances in km. Tracker records must be submitted with each payment claim as confirmation of water being delivered to the specified locations. Tracking data must be made available to the municipality upon request.

4.6. The water tankers must be 16 000 or 18 000 Litres – the proof of the tanker capacity (size) must be provided

5. PROTECTIVE EQUIPMENT

5.1. The Service Provider shall always provide all his/her workers with all necessary full protective clothing for use.

6. WATER SUPPLY POINTS

6.1. Water supply points will be provided with GPS coordinates (where possible) on the attached roasters.

7. SPECIAL CONDTIONS

7.1. The council reserves the right to add to or omit any plant to or from this contract.

8. FACILITIES

9.1. No toilet, water, electricity or storage facilities are available, and the Service Provider is to make his own arrangements with regard thereto.

9. SUPPLY ALL EQUIPMENT

10.1. Service Provider are to supply all equipment required to undertake and complete the work as specified and no additional payments will be entertained.

10. DAMAGE TO INFRASSTRUCTURE

10.1. The apparatus and methods used shall not cause any damage to pipes, manhole, property or fixture and any damage as may be caused will be repaired by the Council at the Service Provider's expense.

11. COMMUNICATION

11.1. The Service Provider is to provide his operational staff with cellular phone for communication and contact purposes for the duration of the contract.

11.2. The Management and the supervisor of the Service provider should be always avail themselves as and when required for the duration of the contract

12. SUBCONTRACTING

12.1. No subcontracting will be allowed.

13. SIGNING OFF OF TASK

13.1 The Service Provider shall, prior to departure from site, advice the relevant Council representative of completion of the task. The Council representative will have sole discretion if the work has been completed satisfactorily and will be required to sign off the work sheet for the task rendered